

Pau de Merenda				

This gold-in-soil anomaly is located approximately 2kms NW of Central along same trend and is 1100 x 650m in extent. Previous garimpo workings are coincident with the soil anomaly which has so far been partially tested by drilling with 5 holes completed to date returning gold only values up to 47m @ 1.76g/t. Drill results for holes drilled on the Pau de Merenda target, 3km NW of the Central zone.

Drill Hole	From (m)	To (m)	Interval Width (m)*	Gold (g/t)
DDH 20	87.8	118	30.2	1.11
	21.3	22.8	1.5	2.13
	76	123.1	47.1	1.76
	143	145	2	1.27
DDH 21	127	127.6	0.6	2.31
	169	169.8	0.8	1.99
DDH 22	4.6	12.2	7.6	1.07
	16.8	18.3	1.5	1.29
	62.8	71.3	8.5	5.07
DDH23	No significant results			
DDH 72	65.9	69.9	4	6.42
DDH 75	95.8	99.8	4	0.68
	240.2	246.2	6	2
DDH 78	151.1	158.2	7.1	2.35
DDH 80	No significant results			
DDH 82	0	18.3	18.3	0.46
DDH 84	101.1	106.6	5.5	0.25

Note: Widths reported in the above table are down hole widths and the true widths are estimated to be between 70 and 90%.